

SDMS US EPA REGION V

COLOR - RESOLUTION - 3

IMAGERY INSERT FORM

Multiple pages of this document include color or resolution variations and may be illegible in SDMS due to bad source documents. Unless otherwise noted, these pages are available in monochrome. (The source document page(s) are more legible than the images.) The original document is available for viewing at the Superfund Records Center.

SITE NAME	SAUGET AREA 1
DOC ID #	153479
DOCUMENT VARIATION	<u> X </u> COLOR OR <u> </u> RESOLUTION
PRP	SAUGET AREA 1
PHASE	SAS
OPERABLE UNITS	
PHASE (AR DOCUMENTS ONLY)	<u> </u> Remedial <u> </u> Removal <u> </u> Deletion Docket <u> </u> <u> </u> Original <u> </u> Update # <u> </u> Volume <u> </u> of <u> </u>
COMMENT(S) VARIOUS SITE MAPS FIGURES: 2-3 & 2-4	

D-2
E1631210002--St. Clair Co.
P.T.s Showclub
IID984809295
Superfund/HRS

9/22/93

153479



CERCLA

Screening Site Inspection Report



**Illinois Environmental
Protection Agency**
P.O. Box 19276
Springfield, IL 62794-9276

TABLE OF CONTENTS

	Page
1. INTRODUCTION.....	1
2. SITE BACKGROUND.....	3
2.1 INTRODUCTION.....	3
2.2 SITE DESCRIPTION.....	3
2.3 SITE HISTORY.....	9
2.4 APPLICABILITY OF OTHER STATUTES.....	12
3. SITE INSPECTION ACTIVITIES AND ANALYTICAL RESULTS.....	14
3.1 INTRODUCTION.....	14
3.2 SOIL SAMPLING.....	14
3.3 FIELD SAMPLING PROCEDURES.....	15
3.4 DECONTAMINATION PROCEDURES.....	18
3.5 ANALYTICAL RESULTS.....	19
3.6 KEY SAMPLES.....	19
4. IDENTIFICATION OF SOURCES.....	22
4.1 INTRODUCTION.....	22
4.2 SAUGET-MONSANTO LANDFILL.....	22
5. MIGRATION PATHWAYS.....	24
5.1 INTRODUCTION.....	24
5.2 GROUNDWATER.....	24
5.3 SURFACE WATER PATHWAY.....	26
5.4 SOIL EXPOSURE PATHWAY.....	28
5.5 AIR PATHWAY.....	29
6. BIBLIOGRAPHY.....	30

APPENDIX

- A. 4-MILE RADIUS MAP
- B. 15-MILE SURFACE WATER MAP
- C. TARGET COMPOUND LIST
- D. BORING LOGS
- E. AERIAL PHOTOGRAPHS
- F. WELL LOGS
- G. EPA FORM 2070-13

LIST OF FIGURES

Figure	Page
2-1.....Site Location Map.....	4
2-2.....Regional Area Map.....	5
2-3..... Site Topography.....	6
2-4.....Wetland Map.....	7
2-5.....Site Map.....	8
3-1.....Sample Location Map.....	21

LIST OF TABLES

TABLE

3-1	Boring Activities	16
3-2	Key Sample Summary	20
3-3	Sample Summary	Appendix D

1. INTRODUCTION

On September 22, 1993, the Illinois Environmental Protection Agency's Pre-Remedial Program was tasked by the U.S. Environmental Protection Agency (USEPA) to conduct a CERCLA Screening Site Inspection (SSI) of the P.T.s Showclub (also known as the Sauget Monsanto Landfill or Site P) (hereinafter referred to as Site P) located within the limits of the village of Sauget, Illinois.

The site was initially placed on the Comprehensive Environmental Response, Compensation and Liability Information System (CERCLIS), on October 26, 1990 as a result of a request for discovery action initiated by the Illinois Environmental Protection Agency (IEPA). The action was taken as a result of the state's concern for the site's potential to allow chemical substances associated with past disposal practices to enter the environment and adversely impact human health and the environment.

The site was initially evaluated in the form of a CERCLA Preliminary Assessment (PA), prepared by Timothy J. Murphy of the IEPA, and was submitted to the Region V offices of the USEPA on September 26, 1991.

In 1986, Ecology and Environment was contracted by the Illinois EPA to conduct sampling activities in the Sauget area. This investigation was undertaken for the purpose of providing additional information on known or suspected contamination sites

within the village of Sauget. Sample results from these sampling event revealed the presence of volatiles, semi-volatiles, inorganic compounds (including lead and cyanide) in surface and/or subsurface soils of Site P. Analytic data obtained over the course of this investigation was used in the preparation of this report.

The purposes of an SSI have been stated by USEPA in a directive outlining Pre-Remedial program strategies. The directive states:

All sites will receive a screening SI to 1) collect additional data beyond the PA to enable a more refined preliminary HRS (Hazard Ranking System) score. 2) establish priorities among sites most likely to qualify for the NPL (National Priorities List). 3) identify the most critical data requirements for the listing SSI step. A Screening SI will not have rigorous data quality objectives (DQOs). Based on the refined factors, the site will then either be designated as SEA (site evaluation accomplished), or carried forward as an NPL listing candidate. A listing SI will not automatically be done on these sites, however. First, they will go through a management evaluation to determine whether they can be addressed by another authority such as RCRA (Resource Conservation and Recovery Act)... Sites that are designated SEA or deferred to other statutes are not candidates for a listing SI.

The listing SI will address all the data requirements of the revised HRS using field screening and NPL level DQOs. It may also provide needed data in a format to support remedial investigation work plan development. Only sites that appear to score high enough for listing and that have not been deferred to another authority will receive a listing SI (USEPA 1988).

The Region V offices of the USEPA have also requested that the Illinois EPA identify sites during the Screening Site Inspection that may require removal action to remediate an immediate human health and /or environmental threat. It is this author's analysis that the site does not pose an immediate threat that would warrant such a response action.

2. SITE BACKGROUND

2.1 INTRODUCTION

This section includes information obtained over the course of the formal CERCLA Screening Site Inspection and previous Illinois Environmental Protection Agency investigation of this site.

2.2 SITE DESCRIPTION

Site P is an inactive, IEPA permitted landfill located in an industrialized and commercialized area of the village of Sauget, Illinois. The triangularly-shaped site covers approximately 20 acres and is situated west of Illinois Route 3 and just north of Monsanto Avenue (See Figures 2-1, 2-2, 2-3, 2-4, 2-5). Site P lies within the southern part of Section 23 and the northern part of Section 26 of Township 2 North, Range 10 West of the Third Principle Meridian in St. Clair County.

Site P is bordered on the west by the Terminal Railroad Association Railroad; on the south by Monsanto Avenue; and on the east by the Illinois Central Gulf Railroad. The two railroads converge to delineate the northern boundary, thus creating the triangulated site. The landfill can be seen during its operation in a 1978 aerial photograph contained in Section D of this report.



FIGURE 2-1
SITE LOCATION





FIGURE 2-2
Regional Area Map
● SITE LOCATION

CERCLA Screening Site Inspection : P.T.s Showclub ILD984809293


FIGURE 2-3



Source: IEPA, 1993. Base Map: Illinois Department of Transportation, 1974.
Scale 1:2000

SITE TOPOGRAPHY

CERCLA Screening Site Inspection: PT's Showclub ILD984809295






FIGURE 2-5
Site Map

The surface of the site is covered with cinder-like material and is vegetated with weeds and small trees. A nightclub, P.T.'s Showclub, is located on the southern portion of the site and covers approximately one acre of the site. The building is rectangular in shape and is approximately 3750 square feet in area. A gravel and asphalt parking lot surrounds the structure. Maps of the site show an unpaved road leading to the northern portion of the site. Access to this road is blocked by posts and chains.

The National Wetland Inventory Maps identify two wetland areas located near the east-central and southwest portions of the site. These areas are approximately three and four acres in size (See Figure 2-4).

Land use in the immediate area south and east of the site is heavy industry and commercial. Undeveloped areas lay generally to the north and west of the site. The nearest individual resident is located approximately 1/4 mile to the northeast of the site.

2.3 SITE HISTORY

According to IEPA Bureau of Land files, operations began at the site in 1972 when Mr. Paul Sauget of Sauget and Company entered into a lease agreement with the Union Electric Company to operate a waste disposal facility. In January of 1973, the IEPA issued an operating permit to Sauget and Company to accept only non-chemical waste from Monsanto. Sauget and Company subsequently applied for

and was granted, a supplemental permit in 1974 which allowed acceptance of general waste and 117,000 cubic yards of diatomaceous earth filter cake from Edwin Cooper, Incorporated (now Ethyl Corporation).

The IEPA began conducting routine inspections of the facility in 1974, at which time no violations were evident. In October of 1975, an inspector observed a small amount of yellowish, tar-like liquid in an area adjacent to several crushed fiber drums which were labelled "Monsanto ACL-85, Chlorine Composition." Sauget and Company and Monsanto were subsequently notified of this permit violation, and the matter was not further addressed. In December of 1977, an inspection revealed the disposal of approximately 25 metal containers (12-15 gallon) full of phosphorus pentasulfide (P_2S_5), a flammable solid. IEPA required Monsanto to excavate and remove all of this material from the site, and to discontinue disposal of any chemical wastes or packages.

During the same inspection, IEPA became aware of another potential problem. A slag pile located on Southern Railway property was being used for intermediate and final cover material at the landfill. Analysis of this slag showed it to be unsuitable as cover due to its high permeability and heavy metal content. Cinders from an unknown source were also being used as cover material at Site P, these materials also increased surface water infiltration and the resulting potential for leaching heavy metals and organic

constituents into the groundwater.

IEPA inspections of the landfill in 1978 and 1979 indicated the continued non-permitted disposal of "Monsanto ACL" filter residues and packages. The composition of this material is not known. According to the site operator at that time, this material would occasionally ignite when it came into contact with the filter cake waste from Edwin Cooper.

An Illinois-American Water Company distribution main was discovered in 1980 during a preparatory landfill excavation on the southern portion of the site. Following discovery of the water line, plans and permits were modified to include no waste disposal within 100 feet of the line. Landfill operations continued until 1984.

IEPA files contain information concerning waste quantities and characteristics for the Edwin Cooper filter cake that was disposed of at Site P. However, Monsanto's wastestream information was never made available to the Illinois Environmental Protection Agency. IEPA records indicate that approximately 117,000 cubic yards of Edwin Cooper filter cake was accepted at Site P. Based on EP toxicity results submitted in 1973, the filter cake was classified as non-hazardous special waste (authorization permit number 740017). According to IEPA Bureau of Land files, additional analytical data is available for a filter cake composite sample from Edwin Cooper in 1979 which indicates elevated levels of lead

at 18.4 parts per million (ppm) cadmium at 1.8 ppm, zinc at 7220 ppm and a Ph of 11.22. No groundwater monitoring program has been established for Site P, nor have wastes at the site been fully characterized.

State and federal aerial photographs that predate the 1970's, show no indications of previous waste disposal activities at the site. Prior to 1979, according to Bureau of Land files, portions of Site P were owned by the Union Electric Company and the Illinois Central Gulf Railroad. Currently, Site P is owned as trust property for Paul Sauget (Chicago Trust and Title) and Union Electric Company in St. Louis.

In 1986, IEPA contracted Ecology and Environment, Incorporated (E&E) to investigate 12 suspected uncontrolled hazardous waste sites and six segments of Dead Creek in Sauget and Cahokia. Site P was among the 12 sites at which soil borings, and subsurface soil samples were collected. The results of E&E's investigation were used in preparation of this report.

2.4 APPLICABILITY OF OTHER STATUTES

As previously mentioned, Site P is an inactive landfill which received municipal, commercial, and industrial wastes from approximately 1972 to its close in 1984. Due to the nature of the materials received and the timeframe of its operational history, the site is not subject to the regulatory requirements of either

the Resource Conservation and Recovery Act (RCRA), the Atomic Energy Act (AEA), Toxic Substances Control Act (TSCA), Federal Insecticide, Fungicide, and Rodenticide Act (FIFRA), or the Uranium Mill Tailings Radiation Control Act (UMTRCA).

3. SITE INSPECTION ACTIVITIES AND ANALYTICAL RESULTS

3.1 INTRODUCTION

This section outlines procedures utilized and observations made during the state financed E&E Sauget Study of 1986. Individual subsections address field sampling procedures, analytical results and key sample summary. The sampling was conducted in accordance with the approved site inspection work plan of 1986, which was developed and submitted to the USEPA Region V offices prior to the initiation of field activities.

3.2 SOIL SAMPLING

During the February 11 and 12, 1987 investigation of Site P, five 30-40 foot soil borings were drilled to investigate subsurface conditions at the site. A total of four samples were taken from these borings. Boring logs indicate that materials within the landfill consisted of silty clay, cinders, slag and refuse which had been disposed directly on the land surface. The thickness of the fill ranges from 13 feet at boring P1 to 28 feet at boring P2. In general, the surface of the site is covered with 1-2 feet of cinders and slag. Fill material was observed at all five boring locations. With the exception of boring P1, fine to medium grained sand was found immediately below the fill in each of the borings. This sand was present to boring termination at 30-40 feet. In P1, five feet of brown silty clay was found to exist between the fill materials and the fine to medium-grained sand. The absence of clay

and the relatively greater thickness of the fill at other boring locations suggests that clay materials may have been scraped from the surface to allow for the disposal of additional debris.

According to E&E, significantly contaminated waste material layers were generally not observed, although air monitoring equipment noted gases in some split-spoon samples containing fill. The boring logs are contained in Appendix F of this report and Table 3-1 details sampling activity at the site.

3.3 FIELD SAMPLING PROCEDURES

Soil borings were drilled using 3 3/4 inch ID hollow-stem augers. Split-spoon samples at 2.5 or 5-foot intervals were collected at all boring locations. Samples were obtained by driving a 2-inch OD standard split-spoon sampler (ASTM D1586) with a 140-pound weight, free-falling 30 inches. The driving resistance was recorded for each 6-inch increment sampled with the split-spoon sampler.

After opening the split-spoon, the samples were screened with a photoionization meter (HNU) for volatile organic compounds, and readings were recorded in a logbook. A visual description of each sample was recorded on field boring logs by the project geologist. The description included the texture, density, structure, color, mineralogy, moisture content, and thickness of the layers, as well as the depth to the water table.

TABLE 3-1

BORING ACTIVITIES

SAMPLE	DEPTH	APPEARANCE	LOCATION
P-1	0-10' 25-35'	Fill Brown, fine, medium sand	Boring located along eastern boundary of site, approx. one-hundred and fifty feet northeast of P.T.s Showclub.
P-2	0-40'	Cinders, debris, silty clay, gray to brown medium sand.	Boring located approx. four-hundred feet to the north of P.T.s Showclub.
P-3	0-30'	Cinders, debris, silty clay and sand	Boring located approx. one-thousand feet to the north of P.T.s Showclub.
P-4	0-10' 25-35'	Fill mixed with fine to medium brown sand	Boring located approx. one-thousand and six-hundred feet to the north of P.T.s Showclub.

The entire contents of each spit-spoon sample was retained and placed in laboratory-cleaned 32-ounce glass jars. To facilitate future sample screening and compositing, field samples from two consecutive split-spoon intervals were stored together in each 32-ounce jar (e.g., samples from the 1 to 2.5 foot and 3.5 to five foot intervals were combined in one 32-ounce jar). The sample jars were suitably boxed, marked, and labeled with the date, boring number, and the depth of each sample within the jar. Immediately following the completion of each boring, samples were screened for organic compounds using an OVA and E&E screening methodology. Following screening, depth intervals from each boring were selected for compositing and chemical analysis, based on screening results and visual observation of samples.

With the exception of P1-53 and P2-54, all samples were composited from depth interval samples collected from within a single boring. In sample P1-53, samples from the 0- to 10-foot depth interval in borings P-1, P-2, P-3, and P-4 were composited; in sample P2-54, samples from the 25- to 35-foot interval were composited from the same four borings. This was done because of the limited number of samples scheduled for Site P during the Sauget sites study performed by E&E under contract with the Illinois EPA and the desire to have chemical data for a wider portion of the site.

Depth interval samples were composited in the following manner:

- * The entire portion of each depth interval to be composited was thoroughly mixed in a clean, stainless steel bowl using a stainless steel tablespoon.
- * Material was chopped, mixed, and stirred until it was reasonably homogenous.
- * A stainless steel tablespoon was used to transfer the material to the appropriate sample containers. A clean stainless steel tablespoon was dedicated for materials for each composite.
- * Sample jars were sealed, labeled, and packaged for shipment as specified in the project QAPP.

3.4 DECONTAMINATION PROCEDURES

Prior to the mobilization of the drill rig on each site, the rig and all associated drilling equipment were thoroughly cleaned with a hot water pressure wash system. All tools and equipment were steam-cleaned between borings to prevent cross-contamination. During drilling, the split-spoon sampler was cleaned between uses by scrubbing with brushes in a trisodium phosphate solution followed by rinses of deionized water, dilute acetone, dilute hexane, dilute acetone, and a final deionized water rinse. Spent decontamination fluids were containerized in a 55-gallon drum.

3.5 ANALYTICAL RESULTS

Analysis of four samples of subsurface soils collected from two borings at Site P revealed the presence of eight volatile compounds present in sample P1-53 and two volatile compounds in sample P-54. No volatiles were detected in samples P5-55 and P5-56. The highest concentrations of any volatile contaminants detected were 0.41 milligrams per kilogram of soil (mg/kg) of toluene and 0.45 mg/kg xylenes in sample P1-53.

Three semi-volatile compounds were found to be present in P1-53. The analysis showed 3.9J mg/kg of phenol, 8.9J mg/kg of 1,4-dichlorobenzene and 3.6J mg/kg of 1,2-dichlorobenzene in the sample. There were no semi-volatiles were detected in samples: P2-54, P5-55, and P5-56. Table 3-2 in Appendix D provides a summary of analytic results.

3.6 KEY SAMPLES

Table 3-3 identifies those samples taken during the CERCLA Screening Site Inspection which were shown to contain contaminants at levels which were significantly higher than found in the established background sample.

TABLE 3-2
KEY SAMPLE SUMMARY TABLE

PT's Showclub ILD984809295		P5-56 2-12-87 Background	P1-53 2-11-87	P2-54 2-11-87	P5-55 2-12-87
SAMPLING POINT PARAMETER					
VOLATILES (PPB)					
Chloroform		50 U	100	--	--
Benzene		50 U	390	--	--
4-Methyl-2-Pentanone		100 U	390	--	--
2-Hexanone		100 U	300	--	--
Toluene		50 U	3300	--	--
Chlorobenzene		50 U	1100	--	--
Ethylbenzene		50 U	950	--	--
Xylene(total)		50 U	3600	--	--
TICs			60	4.0	1.0
SEMI-VOLATILES (PPB)					
Phenol		330.0 U	3100.0 J	--	--
1,4-Dichlorobenzene		330.0 U	7100.0 J	--	--
1,2-Dichlorobenzene		330.0 U	2900.0 J	--	--
Di-n-Butylphthalate		260.0 J	13000.0 J	--	--
Tridecane	--	--	130000.0 J	--	--
Hexadecane	--	--	150000.0 J	--	--
5-Propyl-tridecane	--	--	140000.0 J	--	--
Molecular Sulfur	--	--	85000.0 J	--	--
2,3-Dimethyl Undecane	--	--	--	--	--
Hexadecane	--	--	--	560.0 J	--
TICs		0.0	16.0	10.0	0.0
INORGANICS (PPM)					
Cadmium		1.0 U	3.1	--	--
Lead		72.0 *	--	3.0 *	426.0 *
Mercury		0.1 U	3.1	54	--
Zinc		59.0 *	370.0 *	14.0 *	40.0 *
Cyanide		1.0 U	--	11.0	12.0




FIGURE 3-12 BORING LOCATIONS AT SITE P

FIGURE 3-1
Sample Location Map

4. IDENTIFICATION OF SOURCES

4.1. INTRODUCTION

This section discusses the hazardous waste source which has been identified in the initial stages of the CERCLA Site Investigation.

Information concerning size, volume, waste type and waste composition of the source was compiled during the initial Site Assessment and subsequent Site Inspection. The Sauget-Monsanto Landfill, which comprises Site P, is the only identifiable source at this site.

4.2 SAUGET-MONSANTO LANDFILL

The inactive, unlined Sauget-Monsanto Landfill is approximately 20 acres in size. It was in operation from 1972 to 1984. The property was owned by Union Electric of St. Louis and was leased by Paul Sauget in partnership with Monsanto Chemical.

In 1973, the landfill was permitted to accept only non-chemical waste from Monsanto. However, as previously stated, there were several incidents reported in which other unpermitted wastes were discovered at the site.

File information obtained from the Illinois Environmental Protection Agency indicates that filter cake from Edwin Cooper (now Ethyl Corporation) was also disposed of at the landfill. At times,

the filter cake and waste from Monsanto would come into contact with each other and begin to ignite.

Cinders and fly ash from the Southern Railway slag pile were used for cover material.

The extent of site operations was calculated with the use of aerial photographs of the site. Calculations show that operations extended approximately 2000 feet north of Monsanto Avenue and the area covered by the landfill was approximately 20 acres.

According to wetland maps, there are two wetland areas located on-site, approximately an expression of the groundwater to surface water.

Compounds detected during the E&E sampling event included the following:

5. MIGRATION PATHWAYS

5.1 INTRODUCTION

The CERCLA Site Assessment Program identifies three migration pathways and one exposure pathway by which hazardous substances may pose a threat to human health and/or the environment. Consequently, sites are evaluated on their known or potential impact to these four pathways. The pathways evaluated are groundwater migration, surface water migration, soil exposure, and air migration.

This section presents and discusses information collected during the CERCLA Screening Site Inspection of Site P. This information, together with information documented in other sources, will be utilized in analyzing the site's impact on the four pathways and the various human and environmental targets within the established target distance limits.

Discussions of the pathways will include pathway descriptions, contaminant sources, and targets, such as human populations, fisheries, endangered species, wetlands and other sensitive environments.

5.2 GROUNDWATER

The site is located in an area known as the American Bottoms. ISGS well logs indicate that the upper stratigraphy in this area consists of 70-120 feet of unconsolidated alluvium and glacial

outwash overlying Mississippian-aged limestone and sandstone formations (Ste. Genevieve and St. Louis Limestones). The valley fill deposits are composed of two formations, the uppermost being the Cahokia Alluvium followed by the Mackinaw Member of the Henry Formation.

The Cahokia Alluvium is composed predominantly of silt, clay and fine sand deposits, generally indicative of an aggrading environment. In the vicinity of Dead Creek, these deposits vary in thickness, with a range of 15 to 30 feet. This formation was laid down via flood events, eolian activity, bank slumping, erosion and/or slugs of material deposited directly by tributary streams. The Mississippi River has frequently reworked this formation in such a way that coarser material is intermingled with finer-grained deposits.

Underlying the Cahokia Alluvium is the Mackinaw Member of the Henry Formation. This formation is composed of sand and gravel from glacial outwash. In the Dead Creek area, this material rests directly on the bedrock surface and varies between 70 and 100 feet in thickness. Appendix E contains area well logs which describe the area geology.

Local hydrogeologic information has been obtained through groundwater monitoring in the Sauget area. In the vicinity of Site P, shallow sand and gravel deposits close to the ground surface,

yield significant quantities of water for nearby homes and businesses. Horizontal groundwater movement in the shallow deposits generally follow the land surface topography, with lateral movement toward local discharge zones (wells and small streams), and some movement into the deeper unconsolidated aquifers. Groundwater is encountered between 10 and 28 feet below the ground surface in the Dead Creek area. Under the site, the sand and gravel aquifer (aquifer of concern) is encountered at around 40 feet due to the build up of the landfill. Groundwater in the deeper unconsolidated valley fill deposits generally follows the bedrock surface. Accordingly, groundwater generally flows downstream through the sand and gravel aquifers in much the same direction as the original stream flow, but at a much slower rate.

With regards to the groundwater pathway, residents in the vicinity of the site obtain their water from the Illinois-American Water Company (IAWC). The company obtains water from an intake upstream from Sauget and sells water to the various water departments and districts within the Sauget/Cahokia area. According to Bureau of Land files, some area residents obtain water from shallow wells and are believed to be used for irrigational purposes.

5.3 SURFACE WATER PATHWAY

There were no surface water or sediment samples collected during the February 1986 site investigation at Site P.

Site drainage is controlled by the railroad embankments surrounding the site on all sides except the south. A 500-year levee protects the site from the river's flood events. Any drainage that should happen to runoff the site would make its way to the Mississippi River via the American Bottoms Wastewater Treatment Plant (WWTP). A 15-mile surface water map is located in Appendix B of this report. The probable point of entry (PPE) is the American Bottoms outfall at river mile 178.2. The average discharge of the Mississippi River, as measured over a 128 year period at St. Louis, Missouri, is 179,800 cubic feet per second. The 15-mile surface water target distance limit extends to Mississippi River mile 163.2.

Drinking Water Threat

According to IEPA Public Water Supply files, there are no surface water drinking water intakes located within the 15-mile target distance limit. At river mile 149, approximately 28 miles south of the outfall, the village of Crystal City, Missouri (population 4000) utilizes a Ranney well, adjacent to the Mississippi River for drinking water. A Ranney well is assumed to draw in surface water due to its construction and proximity to the river.

On the Illinois side of the Mississippi River, the nearest drinking water intake is located approximately fifty river miles downstream; at river mile 110. The intake supplies water to the village of Chester and surrounding communities in Randolph County.

Environmental Threat & Human Food Chain

According to U.S. Fish and Wildlife Service National Wetland inventory maps, there are two defined wetlands located on-site. They comprise a total area of approximately eight acres.

According to the Illinois Department of Conservation, the Resource Inventory for the Mississippi River between river miles 178-162 show numerous fishing areas, sport fishing areas, important wildlife habitat and bald eagle use (See Appendix #).

5.4 SOIL EXPOSURE PATHWAY

There are approximately 25 employees located on-site at PT's Showclub, and due to the fact that it is a commercial establishment, there are a number of patrons who frequent the establishment. Cinders and ash are known to have been used as final cover at the landfill.

There are no residences, schools or daycares located within 200 feet of the site.

The site is accessible, as there is no permanent fencing which would bar access to the site. The only barrier, a chain between two posts blocks vehicular traffic from accessing the site north of PT's Showclub.

5.5 AIR PATHWAY

Air sampling was not conducted at the site during the sampling event of February 1986. However, the potential for a release to air exists due to the presence of cinders and ash at the surface of the site.

Approximately 183,000 people live within four miles of the landfill in Sauget. The following table provides information concerning populations located within a four-mile radius of the site.

<u>Distance</u>	<u>Population</u>
On a Source	0
Greater than 0-1/4	0
Greater than 1/4 to 1/2	304
Greater than 1/2 to 1 mile	2812
Greater than 1 to 2 miles	36,958
Greater than 2 to 3 miles	61,505
Greater than 3 to 4 miles	81,571

Note: Worker populations are not included.

According to IEPA Bureau of Land files for Site P, the operator of the landfill reported that whenever waste from Edwin Cooper would come into contact with waste from Monsanto, it would ignite.

BIBLIOGRAPHY

- Bureau of the Census. County and City Data Book. 1990 U.S. Census Data.
- Bureau of the Census. 1990 Population and Housing. 1990 U.S. Census Data.
- Ecology and Environment. May 1988, Expanded Site Investigation Dead Creek Project Sites at Cahokia/Sauget, Illinois, prepared for Illinois Environmental Protection Agency, Division of Land Pollution Control.
- Illinois Department of Commerce and Community Affairs, 1988, Illinois Manufacturers Directory, published by Manufacturers' News, Inc.
- Illinois Environmental Protection Agency Bureau of Land Files, file L163120002.
- Illinois Department of Transportation. Aerial Photographs. Division of Highways, Bureau of Location and Environment, Aerial Surveys Section - 1957 & 1988.
- Lutz, Richard W. Illinois Department of Conservation, Division of Planning, Impact Analysis Section Supervisor. June 24, 1991. Personal correspondence.
- Moore, Bonnie. Southwestern Illinois Metropolitan Planning Commission, (618) 344-4250, Telephone interview.
- U.S. Department of the Interior. Water Resources Data - Illinois, Water Year 1989 Volume I. Illinois except Illinois River Basin. U.S. Geological Survey, 1990.
- U.S. Geological Survey, 1974, Monks Mound, IL. Quadrangle (225A), 1982, Granite City, IL-MO Quadrangle (225B), 1974, Cahokia, IL-MO Quadrangle (225C), 1982, French Village, IL Quadrangle (225D), 7.5 Minute Series.
- U.S. Department of the Interior. Fish and Wildlife Service, National Wetlands Inventory Maps: Monks Mound, IL. Quadrangle (225A), Granite City, IL-MO Quadrangle (225B), Cahokia, IL-MO Quadrangle (225C), French Village, IL Quadrangle (225D).

SDMS US EPA REGION V

FORMAT- OVERSIZED - 5

IMAGERY INSERT FORM

The item(s) listed below are not available in SDMS. In order to view original document or document pages, contact the Superfund Records Center.

SITE NAME	SAUGET AREA 1		
DOC ID #	153479		
DESCRIPTION OF ITEM(S)	USGS TOPOGRAPHIC MAPS		
REASON WHY UNSCANNABLE	<u> X </u> OVERSIZED	OR	<u> </u> FORMAT
DATE OF ITEM(S)	1982		
NO. OF ITEMS	2		
PHASE	SAS		
PRP	SAUGET AREA 1		
PHASE (AR DOCUMENTS ONLY)	<u> </u> Remedial <u> </u> Removal <u> </u> Deletion Docket <u> </u> AR <u> </u> Original <u> </u> Update # <u> </u> Volume <u> </u> of <u> </u>		
O.U.			
LOCATION	Box # <u> </u> Folder # <u> </u> Subsection <u> </u>		
COMMENT(S)			
PARTIAL COPY			



ILLINOIS ENVIRONMENTAL
PROTECTION AGENCY



SITE NAME P.T.'s Show Club
AKA Site P
SITE ID# 984809293

USGS TOPOGRAPHIC MAPS

225B NAME <u>Granite City, IL-MQ</u> DATE.....1954..... REVISED....1982.....	225A NAME <u>Monks Mound, IL</u> DATE.....1954..... REVISED.1968,1974.....
---	--


225C NAME <u>Cahokia, IL-MQ</u> DATE.....1954..... REVISED.1968,1974.....	225D NAME <u>French Village, IL</u> DATE.....1954..... REVISED.....1982.....
--	--

- LEGEND
- ☒ SITE LOCATION
 - ☐ PUBLIC WELL
 - ☐ NEAREST WELL
 - ☐ SURFACE WATER INTAKE



QUADRANGLE LOCATION

MAP SCALE




Regional Director (ARDE) Region III
U.S. Fish and Wildlife Service
Federal Bldg., Ft. Snelling (AD/BSM)
Twin Cities, Minnesota 55111

wetland boundaries established in the
interpretation. In addition, some small wetlands and those
obscured by dense forest cover may not be included on
this document.

Federal, State and local regulatory agencies with jurisdic-
tion over wetlands may define and describe wetlands in a
different manner than that used in this Inventory. There is
no attempt, in either the design or products of this inven-
tory, to define the limits of proprietary jurisdiction of any
Federal, State or local government or to establish the
geographical scope of the regulatory programs of govern-
ment agencies. Persons intending to engage in activities
involving modifications within or adjacent to wetland
areas should seek the advice of appropriate Federal, State
or local agencies concerning specified agency regulatory
programs and proprietary jurisdictions that may affect
such activities.

**- R20WH
(LINEAR DEEPWATER HABITAT)**

0 - Primarily represents upland areas, but may include unclassified wetlands such as man-modified areas, non photo-identifiable areas and/or unintentional omissions.



ILLINOIS ENVIRONMENTAL
PROTECTION AGENCY

SITE: PT's Show Club AKA
Sauget/Monsanto Ldfl., Site
SITE ILD p
984809293

3: Webster Groves, MO-IL
3ER: 224 D
E: 1974/1988 Wetland

QUAD: Cahokia, IL-MO
NUMBER: 225 C
DATE: 1974/1988 Wetland



TABLE 3-3

SAMPLE SUMMARY

PT's Showclub ILD984809295				
SAMPLING POINT	P5-56 2-12-87 Background	P1-53 2-11-87	P2-54 2-11-87	P5-55 2-12-87
PARAMETER				
VOLATILES (PPB)				
Chloroform	5.0 U	10.0	--	--
2-Butanone (MEK)	21.0 B	150.0 B	64.0 B	--
Benzene	5.0 U	39.0	--	--
4-Methyl-2-Pentanone	10.0 U	39.0	24.0 B	--
2-Hexanone	10.0 U	30.0	2.0 BJ	--
Toluene	5.0 U	330.0	--	--
Chlorobenzene	5.0 U	110.0	--	--
Ethylbenzene	5.0 U	95.0	--	--
Xylene(total)	5.0 U	360.0	--	--
2-Butanol	UNKNOWN>TIC	77.0 J		
TICs		6.0	4.0	1.0
SEMIVOLATILES (PPB)				
Phenol	330.0 U	3100.0 J	--	--
1,4-Dichlorobenzene	330.0 U	7100.0 J	--	--
1,2-Dichlorobenzene	330.0 U	2900.0 J	--	--
Di-n-Butylphthalate	260.0 J	13000.0 J	--	--
bis(2-Ethylhexyl)phthalate	180.0 J	--	--	--
Tridecane	UNKNOWN>TIC	130000.0 J	--	--
Hexadecane	UNKNOWN>TIC	150000.0 J	--	--
5-Propyl-tridecane	UNKNOWN>TIC	140000.0 J	--	--
Molecular Sulfur	UNKNOWN>TIC	85000.0 J	290.0 J	--
2,3-Dimethyl Undecane	UNKNOWN>TIC	--	470.0 J	--
Hexadecane	UNKNOWN>TIC	--	560.0 J	--
TICs	0.0	16.0	10.0	0.0
INORGANICS (PPM)				
Cadmium	1.0 U	3.1	--	--
Lead	72.0 *	--	3.0 *	426.0 *
Mercury	0.1 U	3.1	54.0	--
Zinc	59.0 *	370.0 *		
Cyanide	1.0 U	--	11.0	12.0

TARGET COMPOUND LIST

Volatile Target Compounds

Chloromethane	1,2-Dichloropropane
Bromomethane	cis-1,3-Dichloropropene
Vinyl Chloride	Trichloroethene
Chloroethane	Dibromochloromethane
Methylene Chloride	1,1,2-Trichloroethane
Acetone	Benzene
Carbon Disulfide	trans-1,3-Dichloropropene
1,1-Dichloroethene	Bromoform
1,1-Dichloroethane	4-Methyl-2-pentanone
1,2-Dichloroethene (total)	2-Hexanone
Chloroform	Tetrachloroethene
1,2-Dichloroethane	1,1,2,2-Tetrachloroethane
2-Butanone	Toluene
1,1,1-Trichloroethane	Chlorobenzene
Carbon Tetrachloride	Ethylbenzene
Vinyl Acetate	Styrene
Bromodichloromethane	Xylenes (total)

Base/Neutral Target Compounds

Hexachloroethane	2,4-Dinitrotoluene
bis(2-Chloroethyl) Ether	Diethylphthalate
Benzyl Alcohol	N-Nitrosodiphenylamine
bis(2-Chloroisopropyl) Ether	Hexachlorobenzene
N-Nitroso-Di-n-Propylamine	Phenanthrene
Nitrobenzene	4-Bromophenyl-phenylether
Hexachlorobutadiene	Anthracene
2-Methylnaphthalene	Di-n-Butylphthalate
1,2,4-Trichlorobenzene	Fluoranthene
Isophorone	Pyrene
Naphthalene	Butylbenzylphthalate
4-Chloroaniline	bis(2-Ethylhexyl) Phthalate
bis(2-chloroethoxy) Methane	Chrysene
Hexachlorocyclopentadiene	Benzo(a) Anthracene
2-Chloronaphthalene	3,3'-Dichlorobenzidene
2-Nitroaniline	Di-n-Octyl Phthalate
Acenaphthylene	Benzo(b) Fluoranthene
3-Nitroaniline	Benzo(k) Fluoranthene
Acenaphthene	Benzo(a) Pyrene
Dibenzofuran	Indeno(1,2,3-cd) Pyrene
Dimethyl Phthalate	Dibenz(a,h) Anthracene
2,6-Dinitrotoluene	Benzo(g,h,i) Perylene
Fluorene	1,2-Dichlorobenzene
4-Nitroaniline	1,3-Dichlorobenzene
4-Chlorophenyl-phenylether	1,4-Dichlorobenzene

Acid Target Compounds

Benzoic Acid	2,4,6-Trichlorophenol
Phenol	2,4,5-Trichlorophenol
2-Chlorophenol	4-Chloro-3-methylphenol
2-Nitrophenol	2,4-Dinitrophenol
2-Methylphenol	2-Methyl-4,6-dinitrophenol
2,4-Dimethylphenol	Pentachlorophenol
4-Methylphenol	4-Nitrophenol
2,4-Dichlorophenol	

Pesticide/PCB Target Compounds

alpha-BHC	Endrin Ketone
beta-BHC	Endosulfan Sulfate
delta-BHC	Methoxychlor
gamma-BHC (Lindane)	alpha-Chlorodane
Heptachlor	gamma-Chlorodane
Aldrin	Toxaphene
Heptachlor epoxide	Aroclor-1016
Endosulfan I	Aroclor-1221
4,4'-DDE	Aroclor-1232
Diieldrin	Aroclor-1242
Endrin	Aroclor-1248
4,4'-DDD	Aroclor-1254
Endosulfan II	Aroclor-1260
4,4'-DDT	

Inorganic Target Compounds

Aluminum	Manganese
Antimony	Mercury
Arsenic	Nickel
Barium	Potassium
Beryllium	Selenium
Cadmium	Silver
Calcium	Sodium
Chromium	Thallium
Cobalt	Vanadium
Copper	Zinc
Iron	Cyanide
Lead	Sulfide
Magnesium	Sulfate

U.S.E.P.A. DEFINED DATA QUALIFIERS

QUALIFIER DEFINITION ORGANICS

- U Compound was tested for but not detected. The sample quantitation limit must be corrected for dilution and for percent moisture. For soil samples subjected to GPC clean-up procedures, the CRQL is also multiplied by two, to account for the fact that only half of the extract is recovered.

- J Estimated value. Used when estimating a concentration for tentatively identified compounds (TICs) where a 1:1 response is assumed or when the mass spectral data indicate the presence of a compound that meets the identification criteria and the result is less than the sample quantitation limit but greater than zero. Used in data validation when the quality control data indicate that a value may not be accurate.

- C This flag applies to pesticide results where the identification is confirmed by GC/MS.

- B Analyte was found in the associated blank as well as in the sample. It indicates possible/probable blank contamination and warns the data user to take appropriate action

- D Identifies all compounds identified in an analysis at a secondary dilution factor. If a sample or extract is re-analyzed at a higher dilution factor as in the "E" flag above, the "DL" suffix is appended to the sample number on the Form I for the diluted sample, and all concentration values are flagged with the "D" flag.

DEFINITION INORGANICS

- Analyte was analyzed for but not detected.
-
- Estimated value. Used in data validation when the quality control data indicate that a value may not be accurate.
-
- Method qualifier indicates analysis by the Manual Spectrophotometric method.
-
- The reported value is less than the CRDL but greater than the instrument detection limit (IDL).
-
- not used

QUALIFIER DEFINITION ORGANICS

- E Identifies compounds whose concentrations exceed the calibration range for that specific analysis. All extracts containing compounds exceeding the calibration range must be diluted and analyzed again. If the dilution of the extract causes any compounds identified in the first analysis to be below the calibration range in the second analysis, then the results of both analyses must be reported on separate Forms I. The Form I for the diluted sample must have the "DL" suffix appended to the sample number.

- A This flag indicates that a TIC is a suspected aldol concentration product formed by the reaction of the solvents used to process the sample in the laboratory.

- M not used

- N not used

- S not used

- W not used

- * not used

- + not used

DEFINITION INORGANICS

The reported value is estimated because of the presence of interference

Method qualifier indicates analysis by Flame Atomic Absorption (AA).

Duplicate injection (a QC parameter) not met.

Spiked sample (a QC parameter) recovery not within control limits.

The reported value was determined by the Method of Standard Additions (MSA).

Post digestion spike for Furnace AA analysis (a QC parameter) is out of control limits of 85% to 115% recovery, while sample absorbance is less than 50% of spike absorbance.

Duplicate analysis (a QC parameter) not within control limits.

Correlation coefficient for MSA (a QC parameter) is less than 0.995.


Site P Boring logs

Project Name Dead Creek
Project No. IL 3140
Date Prepared 2-11-87
Prepared by Tim Maley

Boring/Well No. P-1
Location Site P
Owner IEPA
Top of Inner Casing Elev. NA
Drilling Firm Fox drilling
Driller Jerry Hammon
Start & Completion Dates 2/11, 2/11/87
Type of Rig Mobile B-61

Depth (ft) Description

Method of Drilling 3 3/4" I.D.
hollow stem augers



WELL DATA

Hole Diam. 8 in.
Boring Depth 35.0 ft.
Casing and Screen Diam. _____
Screen Interval _____
Screen Type _____
Stickup _____
Well Type _____
Well Construction:
Filter Pack _____
Seal _____
Grout _____
Lock No. _____

TEST DATA

Static Water Elev. _____ Date _____
Static Water Elev. _____ Date _____
Slug Test Yes _____ No _____
Test Date _____
Hydraulic Conductivity _____
Other _____

WATER QUALITY

Samples Taken Yes _____ No X
No. of Samples _____
Types of Samples _____

Date Sampled _____
Samplers _____
Samples Analyzed for _____

Split Samples Yes _____ No X
Recipient _____

Comments Subsurface soil samples
from boring 0 - 10' and 25 - 35'
analyzed for HSL compounds.

REMARKS

Ground elev. 418.41

Site Dead Creek Site-P

Boring/Well No. P-1


Sample Depth Blow Count

Description

		Crushed limestone on surface.
1 - 2.5	4-3-3	FILL consisting of black sandy CLAY with crushed limestone, slag gravel, coal, and cinders.
3.5 - 5	4-3-3	Same as above.
6 - 7.5	5-7-25/3	FILL consisting of various debris including paper and plastic products, slag gravel, asphalt, and silty clay. Large obstruction encountered @ 7.5'.
8.5 - 10	6-12-10	FILL consisting of brown silty CLAY with various debris including paper products, small gravel, and fine to coarse grain sand. Wet.
11 - 12.5	6-17-3	Same as above.
		FILL discontinues @ 13.5'
13.5 - 15	3-6-7	Dark brown-dark gray silty CLAY. Slightly mottled. Trace of very fine grain sand. Dry.
16 - 17.5	2-4-6	Same as above to 17'. 4" layer of gray fine grain sand @ 17-17 1/3'. Dry. Then dark gray SILT. Trace of very fine grain sand. Dry.
18.5 - 20	3-5-8	Dark gray very fine grain SAND. Trace of silt. 2" gray silty clay layer @ 19'. Then light gray fine to medium grain SAND. Dry.
21 - 22.5	6-10-12	Brown medium grain SAND. Trace of coarse grain sand and small gravel. Dry.
23.5 - 25	6-13-12	Same as above.
28.5 - 30	2-5-7	Same as above.
33.5 - 35	3-5-10	Same as above. Wet.
		E.O.B. @ 35'.

Project Name Dead Creek
Project No. IL 3140
Date Prepared 2-11-87
Prepared by Tim Maley

Depth (ft) Description



Boring/Well No. P-2
Location Site P
Owner IEPA
Top of Inner Casing Elev. NA
Drilling Firm Fox drilling
Driller Jerry Hammon
Start & Completion Dates 2/11, 2/11/87
Type of Rig Mobile B-61
Method of Drilling 3 3/4" I.D.
hollow stem augers

WELL DATA

Hole Diam. 8 in.
Boring Depth 40.0 ft.
Casing and Screen Diam.
Screen Interval
Screen Type
Stickup
Well Type
Well Construction:
 Filter Pack
 Seal
 Grout
 Lock No.

TEST DATA

Static Water Elev. Date
Static Water Elev. Date
Slug Test Yes No
Test Date
Hydraulic Conductivity
Other

WATER QUALITY

Samples Taken Yes No X
No. of Samples
Types of Samples

Date Sampled
Samplers
Samples Analyzed for

Split Samples Yes No X
Recipient

Comments

REMARKS

Ground elev. 423.62

Site Dead Creek Site-P

Boring/Well No. P-2

Sample Depth Blow Count


Description

		Crushed limestone on surface.
1 - 2.5	6-6-7	FILL consisting of black-brown sandy CLAY with various debris including paper and plastic products, wood chips, slag, small gravel, fine to coarse grain sands, and brick fragments. Dry.
3.5 - 5	3-3-7	Same as above.
6 - 7.5	3-4-4	Same as above.
8.5 - 10	2-6-6	Same as above.
11 - 12.5	5-5-7	Same as above.
13.5 - 15	7-7-8	Same as above.
16 - 17.5	4-3-14	Same as above. Moist.
18.5 - 20	6-6-8	Same as above.
21 - 22.5	6 - 50/3	Same as above. Spoon refusal.
23.5 - 25	10-6-28	Same as above. Poor recovery.
26 - 27.5	3-5-5	No recovery. Probably same as above.
		FILL apparently discontinues @ 28'.
28.5 - 30	6-9-12	Dark gray fine to medium grain SAND. Moist.
33.5 - 35	7-11-10	Brown medium grain SAND. Wet.
38.5 - 40	7-12-14	Dense brown fine to medium SAND. Wet.
		E.O.B. @ 40'.

Project Name Dead Creek
Project No. IL 3140
Date Prepared 2-11-87
Prepared by Tim Maley

Depth (ft) Description

P - 3



Boring/Well No. P-3
Location Site P
Owner IEPA
Top of Inner Casing Elev. NA
Drilling Firm Fox drilling
Driller Jerry Hammon
Start & Completion Dates 2/11, 2/11/87
Type of Rig Mobile B-61

Method of Drilling 3 3/4" I.D.
hollow stem augers

WELL DATA

Hole Diam. 8 in.
Boring Depth 30.0 ft.
Casing and Screen Diam. _____
Screen Interval _____
Screen Type _____
Stickup _____
Well Type _____
Well Construction:
 Filter Pack _____
 Seal _____
 Grout _____
 Lock No. _____

TEST DATA

Static Water Elev. _____ Date _____
Static Water Elev. _____ Date _____
Slug Test Yes _____ No _____
Test Date _____
Hydraulic Conductivity _____
Other _____

WATER QUALITY

Samples Taken Yes _____ No X
No. of Samples _____
Types of Samples _____

Date Sampled _____
Samplers _____
Samples Analyzed for _____

Split Samples Yes _____ No X
Recipient _____

Comments _____

REMARKS

Ground elev. 419.36

Site Dead Creek Site-P

Boring/Well No. P-3

Sample Depth Blow Count


Description

		Black cinder fill on surface.
1 - 2.5	7-9-12	FILL consisting of black and brown sandy clay with various debris material including paper products, wood chips, cloth, tin, rubber, slag, cinders, crushed limestone, an off-white crystalline substance, hay, and fine to coarse grain sand. Dry.
3.5 - 5	3-3-30/6	FILL - same as above.
6 - 7.5	3-3-6	FILL - same as above.
8.5 - 10	6-18-33	FILL - same as above.
11 - 12.5	12-12-13	FILL - poor recovery. Strong moth ball (naphalene) odor.
13.5 - 15	5-7-15	No recovery.
16 - 17.5	6-17-17	FILL - same as above.
		Fill discontinues @ approx. 16.5'.
		Gray silty very fine grain SAND. Dry.
18.5 - 20	5-7-9	Brown fine grain SAND. Dry.
21 - 22.5	4-6-9	Same as above.
23.5 - 25	3-3-5	Same as above. Moist.
26 - 27.5	4-10-8	Same as above. Wet.
28.5 - 30	5-9-11	Same as above. Wet.
		E.O.B. @ 30'

Project Name Dead Creek
Project No. IL 3140
Date Prepared 2-12-87
Prepared by Tim Maley

Depth (ft) Description

P - 4



Boring/Well No. P-4
Location Site P
Owner IEPA
Top of Inner Casing Elev. NA
Drilling Firm Fox drilling
Driller Jerry Hammon
Start & Completion Dates 2/12, 2/12/87
Type of Rig Mobile B-61

Method of Drilling 3 3/4" I.D.
hollow stem augers

WELL DATA

Hole Diam. 8 in.
Boring Depth 35.0 ft.
Casing and Screen Diam. _____
Screen Interval _____
Screen Type _____
Stickup _____
Well Type _____
Well Construction:
Filter Pack _____
Seal _____
Grout _____
Lock No. _____

TEST DATA

Static Water Elev. _____ Date _____
Static Water Elev. _____ Date _____
Slug Test Yes _____ No _____
Test Date _____
Hydraulic Conductivity _____
Other _____

WATER QUALITY

Samples Taken Yes _____ No X
No. of Samples _____
Types of Samples _____

Date Sampled _____
Samplers _____
Samples Analyzed for _____

Split Samples Yes _____ No X
Recipient _____

Comments Subsurface soil samples
from boring 0 - 10' and 25 - 35'
analyzed for HSL compounds.

REMARKS

Slight organic odor.

Ground elev. 424.65

Site Dead Creek Site-P

Boring/Well No. P-4


Sample Depth Blow Count

Description

		Fill material on surface.
1 - 2.5	3-3-5	FILL consisting of dark brown-black silty clay; some crushed limestone, small gravel, and fine to medium grain sand.
3.5 - 5	4-9-8	FILL - same as above with more debris material including paper products and wood chips.
6 - 7.5	3-4-6	FILL - same as above.
8.5 - 10	5-7-22	FILL - same as above.
11 - 12.5	6-7-7	FILL - poor recovery.
13.5 - 15	2-9-5	No recovery.
16 - 17.5	7-14-19	FILL consisting of brown silty CLAY. Some medium-coarse grain sand and small gravel. Trace of a pale yellow solid (hard and brittle) substance. Dry.
18.5 - 20	2-10-2	FILL - same as above. Trace of paper products and wood chips.
21 - 22.5	13-27-17	FILL - same as above with additional debris including asphalt, slag, crushed limestone, wire, and gravel.
23.5 - 25	4-6-8	FILL - same as above.
		Fill discontinues at approx. 26'.
26 - 27.5	3-4-4	Brown fine grain SAND. Trace of silt. Moist.
28.5 - 30	5-10-10	Same as above. Wet.
31 - 32.5	3-6-10	Brown fine to medium grain SAND. Wet.
33.5 - 35	5-10-13	Same as above. Trace of coarse grain sand. Wet.
		E.O.B. @ 35'

Project Name Dead Creek
Project No. IL 3140
Date Prepared 2-12-87
Prepared by Tim Maley

Depth (ft) Description



Boring/Well No. P-5
Location Site P
Owner IEPA
Top of Inner Casing Elev. NA
Drilling Firm Fox drilling
Driller Jerry Hammon
Start & Completion Dates 2/12, 2/12/87
Type of Rig Mobile B-61
Method of Drilling 3 3/4" I.D.
hollow stem augers

WELL DATA

Hole Diam. 8 in.
Boring Depth 35.0 ft.
Casing and Screen Diam. _____
Screen Interval _____
Screen Type _____
Stickup _____
Well Type _____
Well Construction:
 Filter Pack _____
 Seal _____
 Grout _____
 Lock No. _____

TEST DATA

Static Water Elev. _____ Date _____
Static Water Elev. _____ Date _____
Slug Test Yes _____ No _____
Test Date _____
Hydraulic Conductivity _____
Other _____

WATER QUALITY

Samples Taken Yes _____ No X
No. of Samples _____
Types of Samples _____

Date Sampled _____
Samplers _____
Samples Analyzed for _____

Split Samples Yes _____ No X
Recipient _____
Comments Subsurface soil samples
from boring 10 - 25' analyzed for
HSL compounds.

REMARKS

Slight organic odor

Ground elev. 422.98

Site Dead Creek Site-P

Boring/Well No. P-5

Sample Depth Blow Count

Description

		Grass field area on surface.
1 - 2.5	4-5-7	FILL consisting of loose brown-black silty clay with crushed limestone, brick fragments, sand, and small gravel. Dry.
3.5 - 5	4-3-4	FILL - same as above with slag and cinder material.
6 - 7.5	1-2-1	FILL - same as above.
8.5 - 10	1-1-2	FILL consisting of brown-red silty clay. Mottled. Some medium grain sand and small gravel.
11 - 12.5	2-2-2	FILL consisting of brown silty CLAY.
13.5 - 15	1-1-2	FILL - same as above.
16 - 17.5	1-1-1	FILL consisting of brown silty CLAY. Trace of fine grain sand. Moist.
18.5 - 20	1-1-4	FILL - same as above. Trace of small gravel and asphalt.
21 - 22.5	1-2-3	FILL - same as above. Mottled.
		Fill discontinues @ approx. 23'.
23.5 - 25	2-4-7	Light brown fine to medium SAND. Dry.
26 - 27.5	2-4-6	Light brown fine to medium grain SAND. Trace of silt. Dry.
28.5 - 30	2-4-5	Brown fine grain SAND. Wet.
31 - 32.5	6-7-8	Same as above. Trace of coarse grain sand. Wet.
33.5 - 35	7-11-13	Same as above. Trace of coarse grain sand and small gravel. Wet.
		E.O.B. @ 35'


SDMS US EPA REGION V

COLOR-RESOLUTION - 2

IMAGERY INSERT FORM

The following page(s) of this document include color or resolution variations.
 Unless otherwise noted, these pages are available in monochrome. The original document is available for viewing at the Superfund Records Center.


SITE NAME	SAUGET AREA 1
DOC ID #	157439
DESCRIPTION OF ITEM(S)	AERIAL PHOTOGRAPHS (B&W)
PRP	SAUGET AREA 1
DOCUMENT VARIATION	<input type="checkbox"/> COLOR OR <input checked="" type="checkbox"/> RESOLUTION
DATE OF ITEM(S)	2/20/59
NO. OF ITEMS	3
PHASE	SAS
OPERABLE UNITS	
PHASE (AR DOCUMENTS ONLY)	<input type="checkbox"/> Remedial <input type="checkbox"/> Removal <input type="checkbox"/> Deletion Docket <input type="checkbox"/> Original <input type="checkbox"/> Update # <input type="checkbox"/> Volume <input type="checkbox"/> of <input type="checkbox"/>
COMMENT(S)	



Source: IEPA, 1993. Base Map: Illinois Department of
Transportation, February 20, 1959.
Scale: 1"=400'

AERIAL PHOTO

CERCLA Screening Site Inspection: PT's Showclub ILD984809295



Source: IEPA, 1993. Base Map: Illinois Department of
Transportation, March 4, 1975.
Scale: 1"=267'

AERIAL PHOTO

CERCLA Screening Site Inspection: PT's Showclub ILD984809295



Source: IEPA, 1993. Base Map: Illinois Department of
Transportation, April 7, 1978.
Scale: 1"=552'

AERIAL PHOTO

CERCLA Screening Site Inspection: PT's Showclub ILD984809295



Source: IEPA, 1993. Base Map: Illinois Department of
Transportation, January 13, 1986.
Scale: 1"=267'

AERIAL PHOTO

CERCLA Screening Site Inspection: PT's Showclub ILD984809295

Plotted in Carbon Quad.

437

LOG OF WATER WELL

Property owner Midwest Rubber Co. Well No. 24East St. LouisDilled by _____ Year 1951

Formations passed through	Thickness	Depth of Bottom
<u>Clay</u>	<u>7</u>	<u>7</u>
<u>Dry yellow sand</u>	<u>21</u>	<u>28</u>
<u>Building sand</u>	<u>17</u>	<u>45</u>
<u>Fine gray sand</u>	<u>9</u>	<u>54</u>
<u>Med. Coarse sand</u>	<u>6</u>	<u>60</u>
<u>Ext. fine very dirty sand + silt</u>	<u>18</u>	<u>78</u>
<u>Coarse sand + pebbles</u>	<u>32</u>	<u>110</u>

[Continue on back if necessary]

Dished in _____ to _____ ft.

Dished with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

e hole below casing _____ inch. Static level from surf. 36' 10" ft.

Dished capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. _____ in. _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26Description of location _____ Twp. 2NLocation by known location _____ Rge. 10WCounty St. ClairIndex: NO ENVELOPE 26-2N-10W

Property for Illinois State Geological Survey

QUE ED AND MAIL ORIGINAL TO STATE
HEALTH PROTECTION, 535 WEST
DO NOT STACH GEOLOGICAL/WATER
PROPER LOCATION.

GEOLOGICAL AND WATER SURVEYS WELL RECORD

Completed 4-12-76

10. Property owner Clayton Chemical Co. Well No. _____Address 401 S. Brentwood Clayton, Mo.Driller Charles Miller License No. 102-5011. Permit No. 45480 Date 3-22-7612. Water from Land & gravel 13. County St. Clairat depth 40 to 78 ft. Sec. 264. Screen: Diam. _____ in. Twp. 2NLength: 10 ft. Slotted ☒ Rge. 10W

Elev. _____

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (ft.)	To (ft.)
<u>10 7/8</u>	<u>PVC</u>	<u>0</u>	<u>78</u>

SHOW
LOCATION IN
SECTION PLAT562'SL, 587'WL
SW (permit)6. Size Hole below casing: 10 in.7. Static level 15 ft. below casing top which is 1 ft.above ground level. Pumping level _____ ft. when pumping at 200+

gpm for _____ hours. Sub. pump set at 60'.

8. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>Clay</u>	<u>40</u>	<u>40</u>
<u>Land & gravel</u>	<u>38</u>	<u>78</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Robert W. Miller DATE 5-4-76

ST. CLAIR

COUNTY No. 240???

26-2N-10W

1589 435 Drilled in California Quad. LOG OF WATER WELL

Property owner Midwest Rubber, Reclaiming Co. Well No. 2

Drilled by Thorge (Morgan) Year ?

Formations passed through	Thick-ness	Depth of Bottom
<u>Sandy soil</u>	<u>27</u>	<u>27</u>
<u>Loose silt</u>	<u>8</u>	<u>35</u>
<u>Coarse sand + pea gravel</u>	<u>8</u>	<u>43</u>
<u>Ft. fine sand + silt</u>	<u>21</u>	<u>64</u>
<u>Very coarse sand</u>	<u>6</u>	<u>70</u>
<u>Coarse sand, wood, veg., etc.</u>	<u>11</u>	<u>81</u>
<u>Very coarse sand</u>	<u>5</u>	<u>86</u>
<u>Very coarse sand + gravel</u>	<u>28</u>	<u>114</u>

[Continue on back if necessary]

Finished in _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 25' 6" ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. _____ in. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26

Description of location _____ Twp. 2N

Location by _____ Rge. 10W

Signed _____ County Ill. Clair

Copy for Illinois State Geological Survey NO ENVELOPE Index: 26-2N-10W

LOG OF WATER WELL

Property owner Midwest Rubber, Reclaiming Co. Well No. 3

Drilled by Thorge (Morgan) Year 1951

Formations passed through	Thick-ness	Depth of Bottom
<u>Hard fill</u>	<u>3</u>	<u>3</u>
<u>Fine log sand + silt</u>	<u>34</u>	<u>37</u>
<u>Med. fine sand very dirty</u>	<u>14</u>	<u>51</u>
<u>Med. coarse sand, dirty</u>	<u>11</u>	<u>62</u>
<u>Building sand some fine gravel</u>	<u>9</u>	<u>71</u>
<u>Clean coarse sand</u>	<u>23</u>	<u>94</u>
<u>Coarse sand + boulders</u>	<u>8</u>	<u>102</u>
<u>Med. coarse sand</u>	<u>10</u>	<u>112</u>

[Continue on back if necessary]

Finished in _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 35' ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. _____ in. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26

Description of location _____ Twp. 2N

Location by _____ Rge. 10W

Signed _____ County Ill. Clair

Copy for Illinois State Geological Survey NO ENVELOPE Index: 26-2N-10W

Plotted on photo LOG OF WATER WELL

M.C. 22

Property owner Monaco Chemical Co. Well No. 20
 of sec. 81 in plant 15'E. from R.R. spur.
 d by Laguer-Weston (Milliken) Year 7-13-49

Formations passed through	Thick-ness	Depth of Bottom
ay	1	1
inders	1	2
lay	2	5
ndy clay	26	31
edi. fine sand	30	61
nd. sand, gray	13	74
nd. to coarse sand	5	79
oh + coarse sand	2	81
coarse sand	3	84
re sand + gravel + small rocks	19	103

[Continue on back if necessary]

shed in _____ to _____ ft.

d with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

hole below casing _____ inch. Static level from surf. _____ ft.

ed capacity _____ gal. per min. Temperature _____ °F.

er lowered to _____ ft. _____ in. in _____ hrs. _____ min.

th of test _____ hrs. _____ min. Screen Shutter

Diam. _____ Length 25 Bottom set at _____ ft.

[Show location in Section Plat]

anship name _____ Elev. _____ Sec. 26

ription of location SW NE Sec. 26 Twp 2 N

T 2 N, R 10 W Rge. 10 W

ed _____ County S. T. Co.

PLAIP NO ENVELOPE 26-2N-10W

for Illinois State Geological Survey Index:

Plotted on photo IF 89 LOG OF WATER WELL

line log # 437

Property owner Midwest Rubber Claiming Co. Well No. 1

Drilled by Thayer (Morgan) Year ?

Formations passed through	Thick-ness	Depth of Bottom
Sandy loam	10	10
dry sand	14	24
Coarse sand	14	38
Coarse sand, some gravel	4	42
Fine sand	24	66
Ext. fine sand	8	74
Coarse sand + boulders	8	82
Very coarse sand + gravel	24	106

[Continue on back if necessary]

Finished in _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 28' 2" ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. _____ in. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26

Description of location _____ Twp 2 N

_____ Rge. 10 W

ed _____ County Clain Co.

Signed _____ ENVELOPE

Copy for Illinois State Geological Survey Index:

26-2N-10W

LOG OF WATER WELL

#17

Property owner Monsanto Chem. Co.Well No. 9Drilled by H.L. Watson (Walg)Year July 1941

Formations passed through	Thick- ness	Depth of Bottom
Fill	10	10
Mud	8	18
Yellow sand	10	28
Gray sand (getting coarser)	35	63
#30 sand	15	78
#40 gravel	5	83
#50 "	5	88
#60 "	17	105 TD

[Continue on back if necessary]

Finished in _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 30 ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. _____ in. _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen JohnsonSlot 40 Diam. 16 Length 30 Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26Description of location SW, NE Sec. 26, Twp. 2NT 2N, R 10WLocation by Groundwater Div. 61stSigned E. CLAIR County St. ClairCopy for Illinois State Geological Survey NO ENVELOPE Index: 26-2N-10W

Plotted on photo

LOG OF WATER WELL

Property owner Monsanto Chem. Co.Well No. 19(80' S + E of main entrance gate)
Drilled by Wayne Western (Z. Salter)Year Aug. 1948

Formations passed through	Thick- ness	Depth of Bottom
Cinder + clay fill	2	2
Brown sand	14	16
Brown + blue clay	2	18
Brown silty sand	27	45
Med. gray sand	5	50
Med. fine clammy gray sand	5	55
Med. coarse sand + gravel, much rotten wood	6	61
Coarse sand + gravel	5	66
Black med sand, some gravel	7	73
Coarse sand + gravel	2	75
Coarse brown sand	5	80
Med. brownish gray sand + boulders	4	84
Coarse gray sand	10	90
" " " + gravel	18	108

[Continue on back if necessary]

Finished in _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. _____ in. _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen ShuttleSlot _____ Diam. _____ Length 25 Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 26Description of location NE, NE Sec. 26, Twp. 2NT 2N, R 10WSigned _____ County St. ClairCopy for Illinois State Geological Survey NO ENVELOPE Index: 26-2N-10W

LOG OF WATER WELL

Property owner Monsanto Chem. Co. Well No. 15Drilled by H. L. Watson (Watson) Year Feb. 1941

Formations passed through	Thick- ness	Depth of Bottom
clay	70	
fine sand	5	75
fine sand + gravel	5	80
fine sand + gravel	5	85
" " "	5	90
fine sand	5	95
fine sand + gravel	5	100
" " "	5	105
sand + gravel	1 1/2	106 1/2

(Continue on back if necessary)

Lashed in COUNTY No. 1945 to TD ft.Cased with inch from 0 to TD ft.and inch from TD to TD ft.Size hole below casing inch. Static level from surf. 34' ft.Tested capacity gal. per min. Temperature °F.Water lowered to ft. in hrs. min.Length of test hrs. min. Screen Johnson10-30-100 Diam. 16" Length 25' Bottom set at ft.

(Show location in Section Plat)

Township name Elev. Sec. 26Description of location SW, NE Sec. 26,T 2 N, R 10 W

Location by known water Div.

Signed St. Clair County St. Clair

Copy for Illinois State Geological Survey

Index: 26-2N-10W

LOG OF WATER WELL

#16

Property owner Monsanto Chem. Co. Well No. 7Drilled by Watson (Waly) Year June 1941

Formations passed through	Thick- ness	Depth of Bottom
fill	10	10
sand	8	18
fine yellow sand		
sand	20	38
gravel	38	76
fine gravel	5	81
gray gravel	10	91
gravel	10	101
gravel	5	106

(Continue on back if necessary)

Finished in TD=106' at TD to TD ft.Cased with inch from 0 to TD ft.and inch from TD to TD ft.Size hole below casing inch. Static level from surf. 30 ft.Tested capacity gal. per min. Temperature °F.Water lowered to ft. in hrs. min.Length of test hrs. min. Screen JohnsonSlot Diam. 16" Length 30' Bottom set at ft.

(Show location in Section Plat)

Township name Elev. Sec. 26Description of location SW, NE Sec. 26,T 2 N, R 10 W

Location by known water Div.

Signed St. Clair County St. Clair

Copy for Illinois State Geological Survey

Index: 26-2N-10W




ILLINOIS GEOLOGICAL SURVEY, URBANA

Strata	Thickness	Top	Bottom
Redish sandy and blue silt		0	15
Grey sand little silt		15	20
Grey sand		20	25
Blue and grey sand		25	30
Fine grey sand		30	35
Fine grey sand and blue silt		35	40
Fine blue and grey sand		40	45
No recovery wash sample. Fine blue and grey sand		40	50
No recovery wash sample. fine blue and grey sand.		50	55
Fine blue sand, No recovery		55	60
Blue sand and wood no recovery		60	65
Grey and blue sand. No recovery		65	70
Fine blue sand. No recovery		70	75
Fine blue sand. No recovery		75	80
Medium blue sand. No recovery		80	85
Mixed grey and blue sand no recovery		85	90
Mixed grey and blue sand. No recovery		90	95
Mixed blue and grey sand. Could not drive sample Barrell. Felt like gravel		95	100
Blue and grey sand. No spoon sample taken.		100	105
Blue and redish sand. no spoon sample taken. Drove casing to 110'4". Set well screen at 108'11". Could not get any deeper as sand was running under casing.		105	110
Total Depth			110'4" TD

Location plat filed.

S.S. # 29900

COMPANY Wabash Drilling Co.
 M Monsanto Chemical Co. NO. SR-2
 DRILLED November 1956 COUNTY NO. 1987
 HORITY Wabash Drilling Co.
 VATION 412'5' refusal (MSL)
 ATION 680'W 90° 10'W longitude, 4310'N
 INTY ST. CLAIR 35' north latitude



Projected 26- 2N-10W

 SR Jack Bufo photo 1F88
 (H Kelly)

Plotted on photo

LOG OF WATER WELL

Property owner Monsanto Chem. Co. (Plant 'B') Well No. 12

Drilled by H. C. Watson

Year

Formations passed through	Thick-ness	Depth of Bottom
No log	70	
Fine sand	5	75
Coarse sand & gravel	5	80
Coarse sand & gravel	5	85
" " " "	5	90
" " " "	5	95
" " " "	5	100
Sand & gravel	5	105
" " " "	5	110
Fast boulders	2	112

(Continue on back if necessary)

Finished in _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 39'6" ft.

Tested capacity 1250 gal. per min. Temperature _____ °F.

Water lowered to _____ ft. _____ in. _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot 60-80-100 Diam. 16 Length 27 1/2' Bottom set at _____ ft.

(Show location in Section Plat)

Township name _____ Elev. _____

Description of location SE, NE Sec. 26

T 2 N R 10 W

Location by Brown & Co. 8-56 St. Clair

Signed E. CLAIR County No. 26-2 OW

Copy for Illinois State Geological Survey Index: 26-2 OW

LOG OF WATER WELL

 Property owner Monserato Chem. Co. Well No. 2

 Drilled by Layne-Western (F. Sallee) Year Feb. 1948

Formations passed through	Thick- ness	Depth of Bottom
inlet fill	8	8
red green clay	4	12
lay black sand turning brown	3	15
black & brown sand w/ clay	5	20
brown sand	10	30
" " turning gray	5	35
into med. gray sand	5	40
med. gray sand	10	50
med. to coarse gray sand	15	65
med. gray sand	5	70
and 4 boulders, blue clay showing	5	75
into med. sand, silt, few boulders	5	80
red sand, some gravel	5	85
red to coarse sand & gravel	15	100
coarse sand, gravel & boulders	8	108
on rock at 108'		

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

COUNTY NO. 1942

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. _____ in. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

 Township name _____ Elev. 410 Sec. 26

 Description of location NE, NE Sec. 26 Twp. 2N
2N, R 10W Rge. 10W

 County St. Clair

No ENVELOPE 26-2N-10W

Index:

LOG OF WATER WELL

 Property owner Monserato Chem. Co. Well No. 4

 Drilled by Layne-Western (F. Sallee) Year Feb. 1948

Formations passed through	Thick- ness	Depth of Bottom
Cinder	1	1
Brown to yellow clay	7	10
Brown sandy clay	20	30
Brown sand clay showing	10	40
Brown, voided sand	3	43
Med. sand, some gravel, clay showing	7	50
Fine, voided sand & gravel	10	60
Med. sand, some coarse gravel - wood at 68-70	5	70
Med. sand, some gravel	5	75
Fine to coarse sand & gravel, some shells	10	85
Medium fine sand, some gravel	5	90
Medium to coarse sand & gravel boulders	19' 8"	109' 8"
on rock at 109' 8"		

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

COUNTY NO. 1943

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. _____ in. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

[Show location in Section Plat]

 Township name _____ Elev. _____ Sec. 26

 Description of location NE, NE Sec. 26 Twp. 2N
2N, R 10W Rge. 10W

 County St. Clair

No ENVELOPE 26-2N-10W

Index:

LOG OF WATER WELL

Projected 26-2N-10W

LOG OF WATER WELL

Best well

CLAIR NO ENVELOPE
Copy for Illinois State Geological Survey Index: 26-2-10W

Copy for Illinois State Geological Survey

LOG OF WATER WELL

Property owner Levin-Mathis Well No. _____

Drilled by H.L. Watson (Moll) Year June 1948

Formations passed through	Thick- ness	Depth of Bottom
fine sand	3	3
" "	12	15
" " + gravel	20	35
" " + gravel	10	45
" " + gravel	2	47
" " + gravel	1	48
" " + gravel	4	52
" " " " + rock	10	62
" " " "	8	70
" " " "	5	75
" " " " + rock	5	80
" " " "	5	85
" " " "	5	90
" " " "	5	95
" " " "	1	96
" " " "	5	101

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. _____ Length _____ Bottom set at _____ ft.

(Show location in Section Plat)

Township name _____ Elev. _____ Sec. 26

Description of location NF, SW Sec. 26 Twp. 26

T 2 N, R 10 W Rge. 10 W

Location by Dr. Watson Dr. _____

Signed _____ County _____

CLAIR No ENVELOPE Index: 26-2N-10W

For Illinois State Geological Survey

LOG OF WATER WELL

Property owner Levin-Mathis - Monahan, Ill. Well No. _____

Drilled by H.L. Watson (graves) Year Feb. 1947

Formations passed through	Thick- ness	Depth of Bottom
fine sand	20	20
fine sand + gravel	8	28
good formations	26	104 TD

COUNTY No. 1936

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot 30 Diam. 12" Length 26'5" Bottom set at _____ ft.

(Show location in Section Plat)

Township name _____ Elev. _____ Sec. 26

Description of location NF, SW Sec. 26 Twp. 26

T 2 N, R 10 W Rge. 10 W

Location by Dr. Watson Dr. _____

Signed _____ County _____

CLAIR No ENVELOPE Index: 26-2N-10W

For Illinois State Geological Survey

ILLINOIS GEOLOGICAL SURVEY, URBANA


Page 2

ILLINOIS GEOLOGICAL SURVEY, URBANA

RMIT # NF 08825	Thickness	Top	Bottom
4" test hole was first drilled to a depth of 111', then filled in with sand and later re-drilled with a bigger bit. Both records follow.			
ST HOLE			
ay		0	11
lty sand brown		12	21
ne sand brown		22	30
ne sand gray		31	41
dium sand gray		42	51
arse sand gray with pea gravel		52	56
arse sand gray with pea gravel		57	61
arse sand gray with pea gravel		62	86
ry coarse sand gray with 3/8" gravel		87	91
ry coarse sand gray with 1/2" gravel		92	96
ry coarse sand gray with 1/2" gravel		97	101
ry coarse sand gray with 1/2" gravel		102	104
ry coarse sand gray with 1/2" gravel		105	111
			TD
LL RECORD			
ay		0	18
nd coarse gray			20
nd coarse gray with gravel			25
nd fine			30
nd coarse gray with gravel			35
nd coarse gray with gravel			40
nd coarse gray with 1" gravel			45
nd coarse gray with 1" gravel		55	60
nd coarse gray with 3/4" gravel		65	70

	Thickness	Top	Bottom
Sand very coarse gray			75
Sand very coarse gray with cobbles to 5"		80	110 1/2 TD
Well Casing:			
Material - Steel coated with bituminous			
Diameter: 20" outside diameter			
Length - 78.73'			
Wall Thickness - .075			
Final Casing Elevation Above Grade: 1'			
Size of Drilled Hole:			
40" to 20"			
38" to bottom			
Well Screen:			
Material - Stainless steel #304			
Diameter - 20" nominal			
Length - 31.82			
Slot Size - .100			
Type Make - UOP Johnson			
Depth of Screen set at 110.55'			
Gravel Filter:			
Used 23 tons Muscatine, 1/16" - 3/16"			
No. 3			
Wall Thickness - 8 1/2"			
Feet Above Screen - 26'			
Static Level: 23.86'			
S.S. # 57106.			

ANY Luhr Brothers, Inc.
 Cerro Copper & Brass Co. NO. 1
 DRILLED July 10, 1970 COUNTY NO. 3208
 ORITY Company
 ATION
 TION 1000' line, 400' W line of NW
 TY ST. CLAIR



26-2N-10W

Luhr Bros., Inc.
 ST. CLAIR

Cerro Copper & Brass Co.
 26-2N-10W



E. St. Louis-Monsanto P. O.

ANY F. Thorpe-Engineer

Evans-Wallower Zinc Co. 2

ORITY F. Thorpe

ATION

ECTOR

IDENTIAL

DATE DRILLED March 1929

Map No. 4W
R. 10W

T	2N	Sec. 24 ?

COUNTY NO. 1740	STRATA		Thickness		Depth	
	Feet	In.	Feet	In.	Feet	In.
Subsoil & clay	16		16			
Sand, extremely fine	11		27			
Sand, very fine, loamy	8		35			
Sand, very fine	11		46			
Sand, fine	6		52			
Sand, very fine	3		55			
Sand, fine, gritty	7		62			
Boulders up to 4" with some sand	5		67			
Regular building sand	14		81			
Sand, medium coarse	2		83			
Sand, very coarse	19		102			

"During the month of March, 1929, I installed a porous concrete well 30" I.D. and 40" O.D. at the plant of the Evans-Wallower Zinc Co. at Monsanto P.O., East St. Louis, Ill. and the above is the log of all the strata we went through in Well #2.

"The static level of water varies with the river level."
(Letter of F. Thorpe rec'd. 4-3-29)

NO ENVELOPE

County St. Clair

Index No.

04W24

—DRILL RECORD

24-2N-10W



TOWN East St. Louis

COMPANY Thorpe Concrete Well Co.

FARM Certain-teed Products No. 3

AUTHORITY Written log

ELEVATION 416 topo.

COLLECTOR Ireland DATE DRILLED 4-34

CONFIDENTIAL 18th and Broadway

Map No. 4W
R. 10W

T. 2		Sec. 14
N		

No.	COUNTY NO. 1739	STRATA		Thickness		Depth	
		Feet	In.	Feet	In.	Feet	In.
		6		6			
		4		10			
		7		17			
		10		27			
		13		40			
		13		53			
		7		60			
		4		64			
		26		90			
		2		92			
		9		101			
		6		107			
		2		109			
		7		116			

Baits drilled 3 wells

1-21
7-17
11-17

120
120
119

NO ENVELOPE

County ST. CLAIR

Index No.

04W24

T.—DRILL RECORD

24-2N-10W

TOWNSHIP MAP No. 4W
 PANY Union Electric Light and Power LOW
 300 ft. S. of North property Line
 50 ft. E. of Eastern Inner 2
 HARBOR Harbor Line N
 HOLE No. 6
 DATE DRILLED
 PROJECT 23

COUNTY NO. <u>182</u> STRATA	THICKNESS		DEPTH	
	FEET	IN.	FEET	IN.
Water	16		16	
Sand, fine	12		28	
Sand, coarse	10		38	
Sand, very coarse	10		48	
1/2 in. gravel				
Sand, coarse	27		75	
Sand, coarse	4		79	
5% 1/2 in. gravel				
Sand, coarse	4		89	
25% 1/2 in. gravel				
Sand, coarse	3		92	
40% 3 in. gravel				
Sand with gravel	12	8	104	8
Minus 76.06 rock				



TOWN **Cahokia** TOWNSHIP **MAP No. 4W**
 COMPANY **Union Electric Light & Power** **10W**
 FARM **100 ft. S. of N. property Line on**
 AUTHORITY **Eastern Inner Harbor Line.** **2** **Proj.**
 ELEVATION **HOLE No. 7** **N** **23**
 COLLECTOR **DATE DRILLED**

No.	COUNTY NO.	STRATA	THICKNESS		DEPTH	
			FEET	IN.	FEET	IN.
			35		35	
		Sand, fine	5		40	
		Sand, coarse	10		50	
		5% 2 in. gravel				
		Sand, coarse	15		65	
		15% 1/8 in. gravel				
		Sand, coarse	12		77	
		20% 1 1/2 and 10% 1/8 in. gravel				



(575-5M-7-23)

Cahokia TOWNSHIP MAP No. 4W
 Union Electric Light & Power 10W
 100 ft. S. of N. property line
 258 ft. E. of Eastern Inner 2
 Harbor line. HOLE No. 1 N
 DATE DRILLED

1	2	3	4
5	6	7	8
9	10	11	12
13	14	15	16

Proj.
23

COUNTY NO. 1730	THICKNESS		DEPTH	
	FEET	IN.	FEET	IN.
Mud, black and fine sand	30		30	
Sand, fine	4		34	
Sand, coarse	2		36	
5% 1/8 in. gravel				
25% 1/4 in. gravel	2		38	
50% 2 1/2 in. gravel	2		40	
Sand, coarse	8		48	
30% 1/8 to 1 in. gravel				
Sand, coarse	4		52	
10% 1/4 in. gravel				

City St. Clair, Index No. 0464
 DRILL RECORD ILLINOIS STATE Projected 23-2N-10W



(575-5M-7-23)

TOWN Cahokia TOWNSHIP MAP No. 4W
 COMPANY Union Electric Light and Power 10W
 FARM 300 ft. S. of N. Property Line
 AUTHORITY 250 ft. E. of Eastern Inner 2
 ELEVATION Harbor line HOLE No. 2 N
 COLLECTOR DATE DRILLED

1	2	3	4
5	6	7	8
9	10	11	12
13	14	15	16

Proj.
23

No.	COUNTY NO. 1731	THICKNESS		DEPTH	
		FEET	IN.	FEET	IN.
	Sand, fine	10		10	
	Sand, very fine	8		18	
	Mud, black	6		24	
	Mud, black and fine sand	11		33	
	mixed				
	Sand, fine. 10% 1/4 in.	5		38	
	gravel				
	Sand, coarse. 15% 1/2 in.				
	gravel	5		43	
	Sand, coarse	5		48	
	20% 1/2 in. gravel				
	Sand, fine	5		53	
	Sand, coarse. Pieces of				
	soapstone	5		58	
	Sand, coarse	8		66	
	5% 1/4 in. gravel				
	Sand, coarse	6		72	
	10% 1/2 in. gravel				
	Sand, coarse	4		76	
	20% 4 in. gravel				
	Sand, coarse,	15		91	
	20% 3/4 in. gravel				
	Sand, coarse	10		101	
	Minus 73.66 Rock				

County St. Clair, Index No. 0464
 DRILL RECORD ILLINOIS STATE Projected 23-2N-10W

LOG OF WATER WELL

Mr. James
Property owner American Fire Co.
Monroeville, Ill. Well No. 8

Drilled by H. L. Watson Year Feb. 1946

Formations passed through	Thick- ness	Depth of Bottom
<u>Gravel</u>	<u>20</u>	<u>20'</u>
<u>Quick sand</u>	<u>30</u>	<u>50'</u>
<u>Sand</u>	<u>16</u>	<u>66'</u>
<u>Med. Sand</u>	<u>10</u>	<u>76</u>
<u>No log</u>	<u>26</u>	<u>102</u>
TD = 102		

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen Cole

Slot _____ Diam. 1/4 Length 30' Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 23

Description of location SE, SE Sec. 23

T2N, R10W

Location by Iron River Water Div.

Signed _____ County St. Clair

Copy for Illinois State Geological Survey No ENVELOPE Index: 23-2N-10W

LOG OF WATER WELL

Property owner American Fire Co.
Monroeville, Ill. Well No. 9

Drilled by H. L. Watson (G. W. Finley) Year Nov. 1950

Formations passed through	Thick- ness	Depth of Bottom
<u>Mud</u>	<u>35</u>	<u>35</u>
<u>Sand</u>	<u>45</u>	<u>80</u>
<u>Medium sand</u>	<u>20</u>	<u>100</u>
<u>sand & coarse gravel</u>	<u>4</u>	<u>104</u>
TD = 104'		

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ from _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. _____ ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot _____ Diam. 40" Length 60' Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 23

Description of location SW, SE Sec. 23

T2N, R10W

Location by Iron River Water Div.

Signed _____ County St. Clair

Copy for Illinois State Geological Survey No ENVELOPE Index: 23-10W

ILLINOIS GEOLOGICAL SURVEY, URBANA

Page 1

ILLINOIS GEOLOGICAL SURVEY, URBANA

INDUSTRIAL Permit #NF4849	Thickness	Top	Bottom
Yellow brown clay		0	10
Medium sand brown		10	25
Medium coarse sand brown		25	30
Coarse sand brown with pea gravel		30	35
Coarse sand brown		35	40
Medium coarse sand brown		40	55
Medium fine sand brown		55	60
Medium sand brown		60	70
Very coarse sand gray with 1 1/2" gravel		70	80
Very coarse sand gray with 1/4" gravel		80	85
Very coarse sand gray with 3/4" gravel		85	90
Very coarse sand gray with 1/2" gravel		90	95
Very coarse sand gray with 3/8" gravel		95	100
Very coarse sand gray with 1" gravel		100	105
Very coarse sand gray with 3/4" gravel		105	107
Very coarse sand gray with 1/4" gravel		107	113
Very coarse sand gray with 1/2" gravel		113	116
			TD
Size of hole 38"			
Casing: 88" - 18" outside diameter steel			
Casing elevation 2' above grade			
Static water level 36.9' top of casing			
26.5 tons gravel pack 11" wall 45' above screen			
Screen: Johnson Stainless Steel 18" nominal diameter. Length 30' set at 116'			
Slot size: .060"			
Two wells 300' apart were drilled under Permit #NF4849			
NO ENVELOPE			
* North Reservoir			

INDUSTRIAL Permit #NF4849	Thickness	Top	Bottom
Brown Clay		0	5
Brown silty sand		5	20
Fine sand brown		20	25
Fine sand gray		25	30
Coarse sand gray with pea gravel		30	35
Medium coarse sand gray		35	40
Coarse sand gray		40	45
Medium fine sand gray		45	55
Very coarse sand gray with pea gravel		55	60
Medium coarse sand gray		60	65
Very coarse sand gray with 3/4" gravel		65	70
Medium coarse sand gray with pea gravel		70	75
Very coarse sand gray with 3/4" gravel		75	110
Very coarse sand gray with 1" gravel		110	115.5
			TD
Size of hole 38"			
Casing: 88.70' - 18" outside diameter steel			
Casing elevation 3.2' above grade			
Static water level 37'			
26.5 tons gravel pack 11" wall 55' above screen.			
Screen: Johnson Stainless Steel 16" nominal diameter. Length 30' set at 115.5'			
Slot size: .060			
Two wells 300' apart were drilled under Permit #NF4849			
NO ENVELOPE			
* Southwest Reservoir S.S.#55983			

ANY Luhr Brothers, Inc.
 Midwest Rubber Reclaiming Co. 10
 DRILLED September 3, 1968 COUNTY NO. 2856
 ORITY Luhr Bros. Inc.
 ATION
 ION Lot 209 Third Subdivision of Cahokia*
 ST. CLAIR Commonfields 237-2N-10 W

COMPANY Luhr Brothers, Incorporated.
 FARM Midwest Rubber Reclaiming Co. 11
 DATE DRILLED September 6, 1968 COUNTY NO. 2857
 AUTHORITY Luhr Bros. Inc.
 ELEVATION
 LOCATION Lot 209 Third Subdivision of Cahokia*
 COUNTY ST. CLAIR Commonfields 237-2N-10W

LOG OF WATER WELL

Platteau
American Fine Co. - Monmouth

322

Property owner United Engineers + Const. Inc. P. St. Louis Well No. 6

Drilled by H. L. Watson (Gardensville) Year Nov. 1942

Formations passed through	Thick- ness	Depth of Bottom
<u>Cinder + Mud</u>	<u>15</u>	<u>15</u>
<u>Fine sand</u>	<u>60</u>	<u>75</u>
<u>good water bearing formation</u>	<u>30</u>	<u>105</u>
<u>Quartzite to soapstone</u>	<u>2</u>	<u>107</u>

Abandoned

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 34 ft.

Tested capacity 1500 gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen Cool

Slot 120 Diam. 16 Length 30' Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. _____ Sec. 23

Description of location SE, SE Sec 23 Twp. 2N

T 2N, R 10W Rge. 10W

Location by known monument 2 lines

Signed _____ County St. Clair

CLAIR Copy for Illinois S Geological Survey NO ENVELOPE 23-2N-10W Index

LOG OF WATER WELL

321

Property owner United Engineers + Const. Inc. P. St. Louis Well No. 7

Drilled by Watson (Merrett + Corlidge) Year Jan. 1942

Formations passed through	Thick- ness	Depth of Bottom
<u>Dirt</u>	<u>5</u>	
<u>Fine sand</u>	<u>45</u>	<u>50</u>
<u>Coarse sand</u>	<u>25</u>	<u>75</u>
<u>gravel</u>	<u>30</u>	<u>105</u>

COUNTY No. 1929

[Continue on back if necessary]

Finished in _____ at _____ to _____ ft.

Cased with _____ inch _____ from 0 to _____ ft.

and _____ inch _____ to _____ ft.

Size hole below casing _____ inch. Static level from surf. 33'6" ft.

Tested capacity _____ gal. per min. Temperature _____ °F.

Water lowered to _____ ft. in _____ hrs. _____ min.

Length of test _____ hrs. _____ min. Screen _____

Slot 40+50 Diam. 16" Length 30' Bottom set at _____ ft.

[Show location in Section Plat]

Township name _____ Elev. 404 Sec. 23

Description of location SE, SE Sec 23, T 2N, R 10W Twp. 2N

Foot N 90° 10' 7000' N 34° 35' Rge. 10W

Location by known monument 2 lines

Signed _____ County St. Clair

CLAIR Copy for Illinois State Geological Survey NO ENVELOPE 23-2N-10W Index